


| SCHEDULE OF QUANTITIES | |
|--|-------|
| REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL ITEM NO. 20201200 | |
| LOCATION | CU YD |
| SPRINGFIELD AVENUE | 34.8 |
| TOTALS | 34.8 |
| SUBBASE GRANULAR MATERIAL, TYPE B ITEM NO. 31101100 | |
| LOCATION | CU YD |
| SPRINGFIELD AVENUE | 87.5 |
| TOTALS | 87.5 |
| CLASS C PATCHES, TYPE IV, 6 INCH ITEM NO. 44201311 | |
| LOCATION | SQ YD |
| PATCH 1 | 43.6 |
| PATCH 2 | 172.4 |
| PATCH 3 | 26.7 |
| PATCH 4 | 29.3 |
| PATCH 5 | 14.2 |
| PATCH 6 | 30.2 |
| TOTALS | 316.4 |



LEGEND

CLASS C PATCHES, TYPE IV, 6 INCH

NOTES

- TWO-WAY TRAFFIC SHALL BE MAINTAINED AT ALL TIMES ON SPRINGFIELD AVENUE.
- EXISTING PAVEMENT THICKNESS MAY DIFFER FROM THE PROPOSED PLAN PATCH THICKNESS. SUBBASE GRANULAR MATERIAL, TYPE B SHALL BE USED TO FILL THE PATCH LOCATIONS TO THE PROPOSED BASE GRADE. THIS MATERIAL SHALL BE MEASURED AND PAID FOR PER THE SPECIFICATIONS. THE COST OF REMOVAL AND DISPOSAL OF VARIABLE EXISTING PAVEMENT THICKNESSES SHALL NOT BE MEASURED FOR PAYMENT BUT SHALL BE INCLUDED IN THE COST OF CLASS C PATCHES OF THE SIZE AND TYPE SPECIFIED.

CLASS C PATCHES, TYPE IV, 6 INCH = 43.6 S.Y.
(PATCH 1) USE PP-2 MIX

CLASS C PATCHES, TYPE IV, 6 INCH = 172.4 S.Y.
(PATCH 2) USE PP-2 MIX

CLASS C PATCHES, TYPE IV, 6 INCH = 26.7 S.Y.
(PATCH 3) USE PP-2 MIX

CLASS C PATCHES, TYPE IV, 6 INCH = 29.3 S.Y.
(PATCH 4) USE PP-2 MIX

CLASS C PATCHES, TYPE IV, 6 INCH = 14.2 S.Y.
(PATCH 5) USE PP-2 MIX

CLASS C PATCHES, TYPE IV, 6 INCH = 30.2 S.Y.
(PATCH 6) USE PP-2 MIX



CITY OF URBANA
PUBLIC WORKS
ENGINEERING DIVISION

DATED: 09/18 DRAWN BY: JGB
DESIGNED BY: DFJ CHECKED BY: CES
CITY SECTION
18-00612-00-PV

2018 FULL DEPTH CONCRETE PATCHING
- PART 2
LOCATION 1 - SPRINGFIELD AVENUE

SHEET NO.
1
OF
3